



- EDGE CONDITION LEGEND**
- ⓔ1 - GRAVEL STOP EDGE METAL, REMOVE EXISTING EDGE METAL, INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM & NEW GRAVEL STOP EDGE METAL W/ FULLY ADHERED FLASHING (SEE DET 0001)
  - ⓔ2 - EXIST. METAL EDGE METAL TO REMAIN (DRIP EDGE OR GRAVEL STOP)
  - ⓔ3 - EXIST. RAISED AREA DIVIDER
  - ⓔ5 - EXIST. RAISED AREA DIVIDER OR EXP. JOINT. REMOVE METAL & WALL FLASHINGS, WHERE EXP JOINT, INSTALL FOAM ROD IN JOINT SPACE PRIOR TO INSTALLING MEMBRANE. INSTALL FULLY ADHERED MEMBRANE UP OVER AND ONTO OPPOSITE FACE AND TIE-INTO FIELD MEMBRANE ON BOTH SIDES
  - ⓔ7 - 1'-6" (H) WALL FLASHING, REMOVE ALL FLASHINGS. FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET 0003)

# ROOF PLAN

## BUILDING 3

UPPER ROOFS (SECTION "A") = 38,482 SQ. FT.  
 LOWER ROOFS (SECTION "B") = 10,840 SQ. FT.  
 LOWER ROOFS (SECTION "C") = 7,046 SQ. FT.



General Notes



DISCLAIMER  
 ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY, AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH DESIGN, DESIGN ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.  
 WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address  
 RoofingProjects-com  
 17 High Street  
 Suite 301  
 Norwalk, CT  
 06851

Project Name and Address  
 2024  
 Cire Equity Produce Row  
 3120 Produce Row  
 Houston, TX 77023

Project	Sheet
Date January 25th, 2024	3
Scale 1/32" = 1'-0"	