



ROOF PLAN

- EDGE CONDITION LEGEND**
- (E1) - 2'-6" (H) TO 3'-0" (HXVARIES) X 1'-3" (W) PARAPET WALL REMOVE EXISTING METAL COPING AND ALL WALL FLASHINGS. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TDP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
 - (E2) - 1'-0" (H) PARAPET WALL REMOVE EXISTING METAL COPING AND ALL WALL FLASHINGS. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TDP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
 - (E3) - 1'-0" (H) WALL FLASHING, REMOVE ALL FLASHINGS FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET. 0002)
 - (E4) - 2'-0" (H) WALL FLASHING, REMOVE ALL FLASHINGS LEAVING METAL COUNTER FLASHING TO REMAIN. FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE OF EXISTING VINYL SIDING (SEE DET. 0003)
 - (E5) - CUT BOTTOM EDGE OF EXISTING VINYL SIDING TO MAINTAIN 8" (H) MIN. WALL FLASHING, REMOVE ALL FLASHINGS FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE OF EXISTING VINYL SIDING (INSTALL NEW "J" TRIM AT BOTTOM CUT EDGE OF SIDING (SEE DET. 0003)
 - (E6) - REMOVE EXIST. DRIP EDGE METAL AND GUTTER INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM, TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW 10" X 10" BOX GUTTER W/ (1) DOWNSPOUTS IN ORIGINAL LOCATIONS & CONFIGURATIONS (SEE DET. 0004)
 - (E7) - 4'-0" (H) TRANSITION BETWEEN ROOF LEVELS REMOVE EXIST. WALL FLASHINGS, INSTALL NEW ADHERED FLASHING FULL HEIGHT AND TIE-INTO FIELD MEMBRANE ON BOTH SIDES OF VERT. TRANSITION

- Penetrations List:**
- Curbs**
- A - 4'x5' RTU
 - B - 4'6"x8' RTU
 - C - 5'x9' RTU
 - D - 8'x38' RTU
 - E - Exhaust Fans on I-Beams with 20 I-Beam Support Posts (round 6"). I-Beams are 20"x46".
 - H - Roof Hatch 3'x5' (Replace)
 - J - 4'x4' RTV
- Pipe Penetrations**
- 1" - 12
 - 2" - 7
 - 3" - 3
 - 4" - 5
 - 5" - 1
 - 1'6"x1'6" RTV - 3
 - 4'x4' Sat Dish Pad - 1 (Set on walk pad)
 - 7'x7' Sat Dish Pad - 1 (Set on walk pad)
 - 3'x3' Sat Dish Pad - 2 (Set on walk pad)
 - 1'x1' RTV - 1
 - 2.5'x2.5' RTV - 2
 - 2'x2' RTV - 3
 - 11" Round Vent Stack - 3
 - 6" Round Vent Stack - 3



DISCLAIMER
ALL DEAD, DESIGNED ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY, AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKS SHALL BE USED BY OR DISCLOSED TO ANY PARTISER, ARRANGEMENTS OR THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address

RoofingProjects-com
17 High Street
Suite 301
Norwalk, CT
06851

Project Name and Address

ACME #1063
3101 NY-22
Patterson, NY 12563

Project	Sheet
Date March 5, 2024	1
Scale 1/16" = 1'-0"	