



- EDGE CONDITION LEGEND**
- E1 - 6'-0" TO 10'-0" (H) (VARIES) WALL FLASHING UP TO METAL RIDGE CAP. REMOVE ALL FLASHINGS AND METAL RIDGE CAP. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND NEW METAL RIDGE CAP TO MATCH EXISTING CONFIGURATION
 - E2 - 4'-0" TO 5'-0" (H) (VARIES) X 1'-4" (W) PARAPET WALL. EXISTING CAST COPING TO REMAIN. REMOVE ALL WALL FLASHINGS. INSTALL 1" +/- FURRING TO FLUSH WALL FACE WITH INSIDE FACE OF CAST COPING W/ 1/2" BENS DECK. INSTALL NEW WOOD BLOCKING AT OUTER FACE OF COPING AND ADHERED WALL FLASHING, UP OVER PLATE AND DOWN FRONT FACE. INSTALL NEW 2" FIBRE FASCIA (SIMILAR TO DET. #001)
 - E3 - 6'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET #002)
 - E4 - CUT BOTTOM EDGE OF EIFS WALL CLADDING TO FACILITATE AN 8" MIN. FLASHING HEIGHT AND SEAL CUT EDGE. REMOVE EXISTING FLASHINGS. INSTALL 8" (9") FULLY ADHERED WALL FLASHING, TERM BAR W/ SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT AT TOP TIGHT TO BOTTOM OF EIFS WALL CLADDING (SEE DET. #002)
 - E5 - 6'-0" TO 10'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS LEAVING METAL COUNTER FLASHING TO REMAIN. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE OF NEW BRIP. EDGE COUNTER FLASHING FOR SHINGLE REPLACEMENT (SEE DET. #003)
 - E6 - FLUSH EXP. JOINT - REMOVE JOINT. INSTALL FDM RDD 1 1/2" X WIDTH OF JOINT AND EXTEND MEMBRANE OVER AND TIE-INTO FIELD MEMBRANE ON BOTH SIDES.

NOTE:
IF MANUFACTURER REQUIRES INTERMEDIATE HORIZONTAL TERM BARS DUE TO VERTICAL FLASHING HEIGHTS, CONTRACTOR TO INCLUDE THESE COSTS IN THE LUMP SUM BID PRICE.

- Penetrations List:**
- Curbs**
- A - 4'x6' RTU
 - H - 3'x3.5' Hatch (Replace)
 - B - 5'x10' RTU
 - C - 5'x5' RTV
 - D - 4.5'x4.5' Duct Vent Curb with Conduits
 - E - 8'x43' RTU
 - F - 3'x5' RTU
 - G - (4) Large Exhaust Fans on top of I-Beam Supports with (4) I-Beam Supports (round 5")

- Pipe Penetrations**
- 1" - 4
 - 2" - 4
 - 3" - 7
 - 4" - 3
- 6" Round Vent Stack - 3
 1.5'x1.5' RTV - 4
 2.5'x2.5' RTV - 7
 4'x4' Sat Dish Pad - 1 (Set on walk pad)
 2'x2' RTV - 5
 2'x2' thru roof duct vent - 1
 2.5'x3' RTV - 2
 7'x10' Sat Dish Pad - 1 (Set on walk pad)
 7'x7' Sat Dish Pad - 1 (Set on walk pad)
 8" Round Vent Stack - 1

ROOF PLAN

General Notes



DISCLAIMER
ALL DEAD, DESIGNED ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKINGS SHALL BE USED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address

RoofingProjects-com
 17 High Street
 Suite 301
 Norwalk, CT
 06851

Project Name and Address

ACME #1054
 136 Lake St
 Midland Park, NJ 07432

Project	Sheet
Date April 5, 2024	1
Scale 1/16" = 1'-0"	