



SECTION A
(61,587 SQ. FT.)

SECTION B
(875 SQ. FT.)

SECTION "C"
(1,200 SQ. FT.)
(ALL SHINGLE AREAS)

ROOF PLAN

PIPE PENETRATION

SIZE	QUANTITY
2" DIA	3
3 1/2" DIA	19
4 1/2" DIA	1

VENT STACKS

SIZE	QUANTITY
8" DIA.	6
4" DIA.	3
12" DIA.	1

FAN CURBS

- 1'-8" X 1'-8" 3(OTY)
- 2'-0" X 2'-0" 9(OTY)

RTU SCHEDULE

- A - 4' X 7'
- B - 5' X 7'-6"
- C - 8' X 47'-6"
- D - 19' X 74'-1" BEAM W/(8) 2'X2' POURABLE SEALER BOXES

ROOF HATCH

- 2'-9" X 3'-3" (REPLACE)
- (WIRE BRUSH AND PAINT GUARDRAIL BETWEEN HATCH AND ROOF EDGE)

OTHER ITEMS

- SAT DISH ON 7'X7' PAD = 1 PROVIDE WALK PAD UNDER DISH
- SAT DISH ON 8'X10' PAD = 1 PROVIDE WALK PAD UNDER DISH
- SAT DISH ON 4'X4' PAD = 1 PROVIDE WALK PAD UNDER DISH
- 8" X 3' POURABLE SEALER BOXES = 2
- 4' X 1' POURABLE SEALER BOXES = 1
- 2" SAFETY RAIL SUPPORTS = 3

EDGE CONDITION LEGEND

- E1 - REMOVE EXIST. FLASHINGS, COPING AND CLEAT, 2'-6" (H) WALL FLASHING INSTALL ADHERED WALL FLASHING OVER EXIST 1'-6" (W) BLOCKING AND DOWN OUTSIDE FACE INSTALL NEW 2 PIECE METAL FASCIA (SEE DET. 0001)
- E2 - REMOVE EXIST. FLASHINGS, COPING AND CLEAT, 3'-0" (H) INSTALL ADHERED WALL FLASHING OVER EXIST 2'-4" (W) BLOCKING AND DOWN OUTSIDE FACE INSTALL NEW 2 PIECE METAL FASCIA (SEE DET. 0001)
- E3 - 3'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS. INSTALL TERM BAR AND SLIP FLASHING TO BACKSIDE OF NEW SHINGLE ROOFING DRIP EDGE METAL (SEE DET. 0002)
- E4 - REMOVE EXIST. WALL FLASHINGS, COPING AND CLEAT, 6' TO 1'-6" (H) VARIES INSTALL NEW ADHERED WALL FLASHINGS UP OVER EXIST 1'-0" (W) BLOCKING AND DOWN OUTSIDE FACE INSTALL NEW 2 PIECE METAL FASCIA (SEE DET. 0001)
- E5 - REMOVE EXIST. DRIP EDGE METAL AND GUTTER. INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW 8" X 8" BOX GUTTER W/ (3) DOWNSPOUTS IN ORIGINAL LOCATIONS (SEE DET. 0003)
- E6 - REMOVE EXIST. FLASHINGS COPING AND CLEAT, 6' TO 1'-4" (H) VARIES INSTALL ADHERED WALL FLASHING OVER EXIST 1'-0" (W) BLOCKING AND DOWN OUTSIDE FACE INSTALL NEW 2 PIECE METAL FASCIA (SEE DET. 0001)
- E7 - 8" (H) WALL FLASHINGS. INSTALL ADHERED WALL FLASHINGS, TERM BAR, SEALANT SURFACE MOUNTED COUNTERFLASHING AND SEALANT (SEE DET. 0004)
- E8 - REMOVE EXIST. FLASHINGS, EDGE METAL AND CLEAT, 8" (H) WALL FLASHING. INSTALL ADHERED WALL FLASHING OVER EXIST 8" (W) BLOCKING AND DOWN OUTSIDE FACE INSTALL NEW 2 PIECE METAL FASCIA (SEE DET. 0001)
- E9 - REMOVE EXIST. FLASHINGS, COPING AND CLEAT, 4' TO 8' (H) VARIES INSTALL ADHERED WALL FLASHING OVER EXIST 8" (W) BLOCKING AND DOWN OUTSIDE FACE INSTALL NEW 2 PIECE METAL FASCIA (SEE DET. 0001)
- E10 - 3'-0" TO 16'-0" (H) (VARIES) WALL FLASHING. REMOVE ALL BASE FLASHINGS, SHINGLES AND UNDERLAYMENT. INSTALL ADHERED FLASHINGS FULL HEIGHT. INSTALL TERM BAR AND SLIP FLASHING TO BACKSIDE OF NEW SHINGLE ROOFING DRIP EDGE METAL (SEE DET. 0002)



No.	Revision/Issue	Date

Firm Name and Address
 RoofingProjects.com
 17 High Street
 Suite 301
 Norwalk, CT
 06851

Project Name and Address
 2024
 ACME #1992
 75 Mayhill St.
 Saddle Brook, N.J.

Project	Sheet
Date April 5, 2024	1
Scale 1/16" = 1'-0"	