



- EDGE CONDITION LEGEND**
- (E1) - 1'-0" (H) TO 3'-0" (HXVARIES) X 1'-0" (W) PARAPET WALL REMOVE EXISTING METAL COPING AND ALL WALL FLASHINGS. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
 - (E2) - 1'-0" (H) X 4'-0" (W) PARAPET WALL REMOVE EXISTING METAL COPING AND ALL WALL FLASHINGS. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
 - (E3) - GRAVEL STOP EDGE METAL, REMOVE EXISTING EDGE METAL, INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM & NEW GRAVEL STOP EDGE METAL W/ FULLY ADHERED FLASHING (SEE DET 0002)
 - (E4) - 1'-0" (H) WALL FLASHING, REMOVE ALL FLASHINGS FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET 0003)
 - (E5) - 5'-0" TO 15'-0" (H) WALL FLASHING, REMOVE ALL FLASHINGS INSTALL FULLY ADHERED NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE OF NEW SHINGLE EDGE METAL INSTALLED AS PART OF SHINGLE REPLACEMENT AND INCLUDED IN THIS SCOPE OF WORK (SEE DET 0004)
 - (E6) - 9'-6" (H) WALL FLASHING, REMOVE ALL FLASHINGS INSTALL FULLY ADHERED NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE OF NEW SHINGLE RIDGE CAP METAL INSTALLED AS PART OF SHINGLE REPLACEMENT AND INCLUDED IN THIS SCOPE OF WORK (SEE DET 0004)
 - (E7) - 1'-0" (H) TO 9'-6" (H) RAKED WALL FLASHING, REMOVE ALL FLASHINGS FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET 0003)
 - (E8) - 3'-0" (H) VERT. TRANSITION BETWEEN ROOF AREAS. REMOVE EXISTING WALL FLASHINGS AND EDGE METAL. INSTALL WOOD BLOCKING AT TOP OF TRANSITION TO MATCH HEIGHT OF NEW ROOF SYSTEM INSTALL ADHERED WALL FLASHING FULL HEIGHT AND TIE-INTO FIELD MEMBRANE ON BOTH SIDES OF VERTICAL WALL

ROOF PLAN

- Penetrations List:**
- Curbs**
 - A - 8'x11' RTU
 - B - Chiller units on top of (4) 5"x5" I-Beam square support posts
 - C - 4'x5' RTU
 - D - 5'x7' RTU
 - H - Roof Hatch 3'x3.5'
 - E - 4'x4' RTV
 - F - Chiller units resting on the same I-Beams with (4) 9"x9" square support posts
 - G - 10'x49' RTU
 - I - 4'x7' RTU
 - J - 5.5'x8' RTU
 - H - 3'3"x3'8" Hatch (Replace)

- Pipe Penetrations**
- 1" - 10
 - 2" - 3
 - 3" - 4
 - 4" - 9
 - 2.5'x3' Through Wall Duct Vent - 10
 - 6"x2' Wall Penetrations with Conducts - 1
 - 2'x2' Utility Hood - 1
 - 2.5'x2.5' Kitchen Exhaust Fan - 1
 - 7'x7' Satellite Dish Pad - 1 (set on walk pads)
 - 1'9"x1'9" RTV - 3
 - 2'x2' Kitchen Exhaust - 2
 - 1'x1' RTV - 6
 - 8" Round Vent Stack 0 4
 - 8" Goose Neck Vent Stack - 1
 - 2'x3' Condenser Unit - 1

General Notes



DISCLAIMER
 ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY, AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.
 WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address
 RoofingProjects-com
 17 High Street
 Suite 301
 Norwalk, CT
 06851

Project Name and Address
 2024
 Shaws #2538
 770 Roosevelt Trail
 Windham, ME 04062

Project	Sheet
Date March 14, 2024	1
Scale 1/16" = 1'-0"	