



### ROOF PLAN

**Roof Section C**

**Pipes**

- 1"- 9
- 3"- 3
- 4"- 12
- 6"- 3
- 1"- 2

**Fan Curbs**

- 2'10"x2'10" Kitchen Exhaust Fan- 2
- 3'x3'- 1
- 2'x2'- 1
- 1'4"x1'4"- 1
- 3'3"x2'9"- Roof Hatch (Replace)
- 1'10"x1'4"- PP 1

**RTU's**

- A - 4'4"x6'
- B - 5'x8'

**Satellite Dishes**

- Satellite Dish Mounted to Interior Parapet Wall- 1
- 3'x3' Base

**Side Curb Mounted Edge Boxes- 4**

- Gutter Mounted Antenna- 1

**EDGE CONDITION LEGEND**

- E1 - REMOVE EXIST. DRIP EDGE METAL AND 6" X 6" GUTTER. INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM AND TO PROMOTE DRAINAGE INTO GUTTER. INSTALL NEW 6" X 6" BOX GUTTER W/ 4"X4" DOWNSPOUTS IN ORIGINAL LOCATIONS (SEE DET. 0001)
- E2 - REMOVE EXISTING FLASHINGS, TERM BAR AND EXIST. ROOF TO WALL EXP. JOINT. INSTALL FOAM ROD 1 1/2 TIMES WIDTH OF JOINT AND INSTALL 1'-4"(H) FULLY ADHERED WALL FLASHING, TERM BAR W/ SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT AT TOP (SEE DET. 0002)
- E3 - REMOVE EXIST. WALL FLASHINGS. INSTALL 9"(H) FULLY ADHERED WALL FLASHING, TERM BAR W/ SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT AT TOP TIGHT TO BOTTOM OF EIFS WALL CLADDING (SEE DET. 0002)
- E4 - REMOVE EXISTING 1'-1" (W) COPING/METAL ROOFING CAP AND ALL FLASHINGS. INSTALL 3'-8" (H) FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW 2 PIECE METAL FASCIA (COLOR TO MATCH EXISTING METAL ROOFING) (SEE DET. 0003)
- E5 - CUT BOTTOM EDGE OF EIFS WALL CLADDING TO FACILITATE AN 8" MIN. FLASHING HEIGHT AND SEAL CUT EDGE. REMOVE ALL WALL FLASHINGS. INSTALL 8"(H) FULLY ADHERED WALL FLASHING, TERM BAR W/ SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT AT TOP TIGHT TO BOTTOM OF EIFS WALL CLADDING (SEE DET. 0003)
- E6 - REMOVE EXISTING 1'-1" (W) METAL COPING AND FLASHINGS. INSTALL 10" TO 2'-8"(H) FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0003)

**Roof Section D**

**Pipes**

- 1"- 5
- 2"- 2
- 3"- 1
- 4"- 3
- 6"- 8

**4" Square PP- 2**

**8" Square PP- 1**

**12"x8" PP- 1**

**Fan Curbs**

- 3'x3'- 1
- 2'x2'- 2
- 16"x16" Kitchen Exhaust Fan-1
- 1'8"x1'8"- 1
- 3'3"x2'9"- Roof Hatch (Replace)

**RTU's**

- A - 4'x7'4"
- B - 4'x6'
- C - 5'x8'

**Satellite Dishes**

- 3'x3' Base- 2
- 4'x4' Base- 1
- 6'x6' Base- 1

**Additional Items**

- Condenser + Satellite Dish on (2) 7'(L) 6x6 Wood Dunnage (Replace Wood & set on walk pad)
- Condenser + Satellite Dish on (2) 10'(L) 8x8 Wood Dunnage (Replace Wood & set on walk pads)
- 9'(L) Steel Railing Edge Protection at Hatch Mounted to the Wall (Remove/Paint/Reinstall)



DISCLAIMER  
ALL IDEAS, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFPROJECTS.COM AND WERE CREATED, INVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIC PROJECT. NONE OF SUCH IDEAS, DESIGN ARRANGEMENTS OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY PURPOSE WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF ROOFPROJECTS.COM.  
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address  
 RoofingProjects.com  
 17 High Street  
 Suite 300  
 Norwalk, CT  
 06851

Project Name and Address  
 2024  
**ACME #1058**  
 125 FRANKLIN TPK.  
 MAHWAH, NJ

Project	Sheet
Date April 5, 2024	<b>3</b>
Scale 1/16" = 1'	