



**EDGE CONDITION LEGEND**

- E1 - 0'-6" (H) TO 2'-0" (H)(VARIES) X 0'-11" (W) PARAPET WALL. REMOVE EXISTING METAL COPING AND WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL MECH ATTACHED 1/2" DENS DECK OVER FLASHING SUBSTRATE. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E2 - 1'-6" (H) WALL FLASHING. REMOVE ALL FLASHINGS AND METAL COUNTER FLASHING. INSTALL MECH ATTACHED 1/2" DENS DECK OVER FLASHING SUBSTRATE. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT AT TOP (SEE DET 0002)
- E3 - REMOVE EXIST. DRIP EDGE METAL AND GUTTER INCLUDING EXISTING WOOD FASCIA. INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM, TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW WOOD FASCIA TO MATCH EXISTING CONFIGURATION. INSTALL NEW 6" X 6" BOX GUTTER W/ DOWNSPOUTS IN ORIGINAL LOCATIONS TO MATCH EXISTING CONFIGURATION (SEE DET 0003)
- E4 - SLOPED WALL W/ ASPHALT ROOF SHINGLES. INSTALL MECH ATTACHED 1/2" DENS DECK OVER SLOPED SHINGLES. INSTALL ADHERED WALL FLASHING OVER ENTIRE REAR SURFACE OF SLOPED WALL AREAS WHERE SHINGLES EXISTED. INSTALL TERM BAR, SEALANT AND SLIP FLASHING UNDER EXISTING METAL CAP. (SEE DETAIL 0004)

General Notes



DISCLAIMER  
 ALL DEAD, DESIGNED ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF RP ROOFING PROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKS SHALL BE USED BY OR DISCLOSED TO ANY PARTISER WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF RP ROOFING PROJECTS.COM.  
 WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

| No. | Revision/Issue | Date |
|-----|----------------|------|
|     |                |      |

Firm Name and Address  
 RoofingProjects-com  
 17 High Street  
 Suite 301  
 Norwalk, CT  
 06851

Project Name and Address  
 2025  
 Acme #2633  
 288 Elm St  
 New Canaan, CT 06840

|                       |       |
|-----------------------|-------|
| Project               | Sheet |
| Date<br>May 15, 2025  | 1     |
| Scale<br>1/8" = 1'-0" |       |

- PENETRATIONS LIST:**  
**CURBS**  
 A - CHILLER UNITS AND LARGE RTU ON 32'X42' I-BEAMS WITH (6) 6" ROUND SUPPORTS AND THE LARGE RTU IS ALSO SITTING ON (2) 3'6"X8'6" DUCT CURBS  
 B - 5'6"X7' RTU WITH (2) 1'X4' DUCTS  
 C - 3'X3' RTV WITH (1) 1'X3' DUCT CONNECTED (DUCT IS 9' LONG)  
 D - 3'X6' RTU  
 E - 5'X7' RTU
- PIPES**  
 1" - 2  
 2" - 2  
 3" - 10  
 4" - 4  
 5" - 3
- SATELLITE DISH PADS (SET ON WALK PADS)**  
 3'X3' - 2  
 7'X7' - 1

- CONDENSER ON 2'X3' PLATFORM - 1**  
**ABANDONED CURBS (REMOVE, CLOSE OPENING IN DECK, INFILL INSULATION TO MATCH HEIGHT OF EXISTING ROOF SYSTEM AND ROOF OVER AREA)**  
 1'X1'6" - 1  
 1'X3' - 1  
 2'X2' - 1  
**2'X2' KITCHEN EXHAUST FAN - 1**
- MISCELLANEOUS ITEMS:**  
 3'X3' RTV - 1  
 2'X2' RTV - 1  
 2'X2' KITCHEN EXHAUST FAN - 1  
 3'X3' KITCHEN EXHAUST FAN - 1  
 8'X8' PITCH BOX - 1

ROOF PLAN