



**EDGE CONDITION LEGEND**

- E1 - 10'-0" (H) X 1'-0" (W) PARAPET WALL  
REMOVE EXISTING METAL COPING, WALL FLASHINGS INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E2 - GRAVEL STOP EDGE METAL, REMOVE EXISTING EDGE METAL, INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM & NEW GRAVEL STOP EDGE METAL W/ FULLY ADHERED FLASHING (SEE DET 0002)
- E3 - REMOVE EXIST. DRIP EDGE METAL AND GUTTER  
INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM, TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW 8" X 8" BOX GUTTER W/ DOWNSPOUTS IN ORIGINAL LOCATIONS TO MATCH EXISTING CONFIGURATION (SEE DET 0003)
- E4 - REMOVE EXISTING WALL FLASHINGS AND METAL COUNTER FLASHINGS. INSTALL 1/2" DENS DECK MECH. ATTACHED TO WALL FACE FULL HEIGHT (APPROX 2'-0") TO BOTTOM OF EXISTING OVERHANG SOFFIT. FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING WITH SEALANT JOINT TIGHT TO EXISTING SOFFIT (SEE DET 0004)
- E5 - 1'-0"(H) WALL FLASHINGS. REMOVE EXISTING WALL FLASHINGS AND METAL COUNTER FLASHINGS. INSTALL 1/2" DENS DECK MECH. ATTACHED TO WALL FACE. FULLY ADHERE NEW WALL FLASHING, INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING WITH SEALANT JOINT TIGHT AT TOP (SEE DET 0004)

NOTE: ON SECTION "A" PROVIDE RAISED OUTER VERTICAL LEG ON GUTTER DUE TO ROOF SLOPE

**PENETRATIONS LIST:**

- PIPE PENETRATIONS**  
 1" - 4  
 2" - 5  
 3" - 8  
 4" - 6

H - ROOF HATCH 3'X3.5' (REPLACE)

A - 22'X8' UNIT ON STEEL COLUMN SUPPORTS W/ RETURN DUCT CURB BELOW  
 6" ROUND I-BEAM SUPPORT POSTS/WALL SUPPORTS - 21  
 SCUPPERS - (9) 1'X1' (4 OF THEM OVERFLOW)

- 1' ROUND VENT STACK - 3
- 2'X2' RTV - 1
- 1'X1' GOOSENECK DUCT CURB - 1
- 6'X6' SAT DISH PAD - 1 (SET ON WALK PADS)
- 5'X5' ROUND SAT DISH PAD - 1 (SET ON WALK PADS)
- 8"X8" PITCH BOX WITH CONDUITS - 1
- 6" ROUND PIPE GOOSENECK WITH CONDUITS - 1
- 4.5'X4.5' SAT DISH PAD - 1 (SET ON WALK PADS)
- 8" ROUND VENT STACK - 1
- 2'X4' DUCT PENETRATION THROUGH WALL - 2

ROOF PLAN



DISCLAIMER  
 ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY, AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKS SHALL BE USED BY OR DISCLOSED TO ANY PARTISAN WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.  
 WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address  
 RoofingProjects-com  
 17 High Street  
 Suite 301  
 Norwalk, CT  
 06851

Project Name and Address  
 2025  
 Safeway #066  
 500 S Royal St  
 Alexandria, VA 22314

Project	Sheet
Date May 7, 2025	1
Scale 1/8" = 1'-0"	