



EDGE CONDITION LEGEND

- E1 - 1'-0" (H) TO 4'-0" (H)(VARIES) X 1'-0" (W) PARAPET WALL. REMOVE EXISTING METAL COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL MECH ATTACHED 1/2" DENS DECK FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E2 - REMOVE EXIST. DRIP EDGE METAL AND GUTTER. INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM. TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW 8" X 8" BOX GUTTER W/ DOWNSPOUTS IN ORIGINAL LOCATIONS TO MATCH EXISTING CONFIGURATION (SEE DET 0002)
- E3 - 4" TO 1'-0" (H) CUT BOTTOM OF VINYL SIDING TO ALLOW FOR 2'-0" (H) FLASHING HEIGHT. REMOVE WALL FLASHINGS AND EDGE METAL. INSTALL MECH ATTACHED 1/2" DENS DECK OVER FLASHING SUBSTRATE. INSTALL FULLY ADHERED NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SLIP FLASHING ATTACHED TO REAR OF EXISTING SIDING LEG TO REMAIN (SEE DET 0003)
- E4 - 1'-0" (H) REMOVE WALL FLASHINGS UP TO BOTTOM EDGE OF METAL ROOF PANELS. LOOSEN BOTTOM EDGE OF METAL ROOF PANELS AS REQ'D. TO INSTALL NEW FLASHING. INSTALL MECH ATTACHED 1/2" DENS DECK OVER FLASHING SUBSTRATE. INSTALL FULLY ADHERED NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SLIP FLASHING ATTACHED TO BOTTOM OF EXISTING METAL ROOF PANELS TO REMAIN RE-SECURE BOTTOM EDGE OF EXISTING METAL ROOF PANELS AND SEAL FASTENERS WITH LIQUID FLASHING (SEE DET 0003)
- E5 - 6'-0" (H) WALL REMOVE WALL FLASHINGS AND EDGE METAL. INSTALL MECH ATTACHED 1/2" DENS DECK FULL HEIGHT OF WALL. INSTALL FULLY ADHERED NEW WALL FLASHING FULL HEIGHT AND TIE-INTO FLASHING FROM OPPOSITE SIDE PRIOR TO INSTALLING NEW FASCIA METAL ON EDGE CONDITION E-1

PENETRATIONS LIST:

- CURBS**
 A - 3'X4' RTU
 B - 4.5'X6' RTU
 C - 7'X5' RTU
- PIPE PENETRATIONS**
 1" - 17
 2" - 8
 3" - 6
 4" - 5
- 9"X9" WALL SUPPORT POSTS - 3
 1.5'X2.5' CURB FOR EQUIPPED SUPPORT - 1
 4'X7.5' RTU CURB CONNECTED TO UNIT ON I-BEAM SUPPORTS - 2
 1" WIDE ROUND VENT STACK - 3
 2'X2' RTV - 7
 1'X1' GOOSENECK PIPE CURB - 2
 1'X1' UTILITY HOOD WITH CONDUITS - 8
 1'X1' CURB - 2
 2'X2' ABANDONED CURB - 1 (REMOVE, CLOSE OPENING IN DECK, INFILL TO MATCH HEIGHT OF EXISTING ROOF SYSTEM AND ROOF OVER AREA)
 2.5'X2.5' KITCHEN EXHAUST FAN - 3
 6'X6' SAT DISH PAD - 1 (SET ON WALK PADS)
 3'X3' SAT DISH PAD - 1 (SET ON WALK PADS)
 10" VENT STACK - 2
 ROOF HATCH 3'X3.5' (REPLACE)

General Notes



DISCLAIMER
 ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH DESIGN, DESIGN ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.
 WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address
 RoofingProjects-com
 17 High Street
 Suite 301
 Norwalk, CT
 06851

Project Name and Address
 2025
 Safeway #1283
 8646 Richmond Hwy
 Alexandria, VA 22309

Project	Sheet
Date May 7, 2025	1
Scale 3/32" = 1'-0"	