



ROOF PLAN

--- CENTERLINE OF 2'-0" WIDE WALKWAY PATH
APPROX. 1,470 LINEAL FEET

EDGE CONDITION LEGEND

- E1 - 1'-1" (H) TO 5'-2" (H)(VARIES) X 1'-1"(W) TO 1'-4"(W)(VARIES) PARAPET WALL REMOVE EXISTING METAL COPING AND WALL FLASHINGS. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E2 - 0'-6" (H) X 0'-7" (W) EXP. JOINT. REMOVE EXISTING WALL FLASHINGS & RAISED EXP. JOINT CAP & JOINT. INSTALL FDM RRD 1 1/2 TIMES WIDTH OF JOINT AND INSTALL FULLY ADHERED FLASHING UP OVER AND DOWN OPPOSITE FACE AND TIE INTO THE FIELD OF ROOF ON BOTH SIDES. FABRICATE AND INSTALL NEW METAL CAP TO MATCH EXISTING CONFIGURATION
- E3 - 6'-4" TO 8'-0" (VARIES) EXISTING SLOPED SHINGLE AREA, WITH 3'-0" TO 7'-0" (H) (VARIES) VERT. PARAPET WALL ABOVE. REMOVE VERTICAL WALL FLASHINGS, LOW COUNTER FLASHINGS AND METAL COPING LEAVING SHINGLES IN PLACE. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER EXISTING SHINGLES AND VERT. FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED NEW WALL FLASHING OVER TOP AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET 0001)
- E4 - 6'-0" TO 7'-0" (H) (VARIES) VERT. WALL W/ ASPHALT SHINGLES TO REMAIN. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER SHINGLES FULL HEIGHT. FULLY ADHERE NEW WALL FLASHING FULL HEIGHT. INSTALL TERM BAR, SEALANT AND SURFACE MOUNTED COUNTER FLASHING WITH SEALANT JOINT AT TOP TIGHT TO EXISTING SOFFIT RETURN (SEE DET 0002)
- E5 - 6'-0" TO 7'-0" (H) (VARIES) VERT. WALL W/ ASPHALT SHINGLES TO REMAIN. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER SHINGLES FULL HEIGHT. FULLY ADHERE NEW WALL FLASHING FULL HEIGHT. INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE OF NEW METAL CAP AT SHINGLE ROOF BUILT-IN GUTTER (SEE DET 0003)
- E6 - 9'-0" TO 16'-0" (H) (VARIES) VERT. WALL W/ ASPHALT SHINGLES TO REMAIN. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER SHINGLES FULL HEIGHT. FULLY ADHERE NEW WALL FLASHING FULL HEIGHT. INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE OF NEW METAL DRIP EDGE FOR SHINGLE ROOF ABOVE (SEE DET 0003)
- E7 - 1'-0" (H) VERT. WALL FLASHING. REMOVE FLASHINGS AND EDGE METAL. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER FLASHING SUBSTRATE. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SURFACE MOUNTED COUNTER FLASHING WITH SEALANT JOINT AT TOP (SEE DET 0002)

NOTE: INSTALL HORIZ. TERM BARS AT POINTS ALONG HEIGHT IF REQUIRED BY MANUFACTURER DUE TO HEIGHT

PENETRATIONS LIST:

- CURBS**
- B - 4'X7' RTU
- C - 6'X9' RTU
- D - 5'6"X7'6" RTU
- EQUIPMENT SUPPORT CURBS**
- CONDENSER ON (2) 3'6" ESC
- CONDENSER ON (2) 13' ESC
- E - RTU ON (2) 12'6" ESC
- F - RTU ON (2) 19'6" ESC
- G - CHILLER UNIT ON (2) 12'6" ESC
- I - CHILLER UNIT ON (3) 12'6" ESC
- RTV**
- A - 6'X9' - 2
- 2'X2' - 9
- 1'9"X1'9" - 6
- 3'X3' - 2
- 3'6"X3'6" - 2
- H - 5'X5'6" - 1
- J - 4'X4' - 2
- 2'6"X2'6" - 2
- K - 5'X5' - 3
- UTILITY HOODS**
- 13'X13' - 11
- 1'6"X1'9" - 1
- 1'3"X2'6" - 5

ABANDONED CURBS (REMOVE, CLOSE OPENING IN DECK, INFILL INSULATION TO HEIGHT OF EXISTING ROOF AND ROOF OVER AREA)

- 3'6"X3'6" - 1
- 1'6"X1'6" - 4
- 1'3"X1'3" - 2
- 2'X2' - 1
- 12'6" ESC - 2
- SATELLITE DISH**
- 2X2 CURB REMOVE

PIPES

- 1" - 5
- 4" - 19
- 5" - 9
- 6" - 2

KITCHEN EXHAUST FANS

- 1'9"X1'9" - 2
- 2'X2' - 2
- 2'6"X2'6" - 1

VENT STACKS

- 1'9"X1'9" - 2
- 2'X2' - 6
- 1'3"X1'3" - 3

ESC PIPE SUPPORTS

- 2'6" ESC - 5

GOOSE NECK VENTS

- 1'9"X1'9" - 2

ROOF HATCH (REPLACE)

- 3'X5'

General Notes



DISCLAIMER
ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF RP ROOFING PROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH DESIGN, DESIGN ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF RP ROOFING PROJECTS.COM.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address
RoofingProjects-com
17 High Street
Suite 301
Norwalk, CT
06851

Project Name and Address
2025
Jewel-Osco #80
2480 Illinois Rte 59
Plainfield, IL 60586

Project	Sheet
Date April 11, 2025	1
Scale 1/16" = 1'-0"	