



# ROOF PLAN

### EDGE CONDITION LEGEND

- E1** - 0'-6" (H) TO 4'-10" (HXVARIES) X 1'-1" (W) PARAPET WALL. REMOVE EXISTING METAL COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL 1/2" MECH ATTACHED DENS DECK OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E2** - 2'-4" (H) TO 3'-5" (HXVARIES) PARAPET WALL. REMOVE EXISTING CLAY TILE COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL NEW 2X12 P.T. BLOCKING ON TOP OF MASONRY WALL. INSTALL 1/2" MECH ATTACHED DENS DECK OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E3** - 4' TO 8" (HXVARIES) X 0'-6" (W) RAISED EXP. JOINT. REMOVE EXISTING WALL FLASHINGS & RAISED EXP. JOINT. INSTALL FOAM ROD 1 1/2 TIMES WIDTH OF JOINT. INSTALL 1/2" MECH ATTACHED DENS DECK ON TOP AND SIDES LEAVING JOINT SPACE OPEN. INSTALL FULLY ADHERED FLASHING UP OVER AND DOWN OPPOSITE FACE AND TIE INTO THE FIELD OF ROOF ON BOTH SIDES.
- E4** - 2'-7" TO 4'-3" (H) VARIES SLOPED TRANSITION BETWEEN ROOF LEVELS. REMOVE EXISTING EDGE METAL, LEAVING EXISTING FLASHINGS IN PLACE. INSTALL 1/2" MECH ATTACHED DENS DECK OVER FLASHINGS FULL HEIGHT. INSTALL NEW WOOD BLOCKING ALONG TOP EDGE TO MATCH HEIGHT OF NEW ROOF SYSTEM. INSTALL FULLY ADHERED FLASHING AND TIE-IN TO FIELD MEMBRANE ON BOTH SIDES OF TRANSITION
- E5** - 7' TO 10' (H) VARIES VERT TRANSITION BETWEEN ROOF LEVELS. EXISTING FLASHINGS TO REMAIN. INSTALL 1/2" MECH ATTACHED DENS DECK OVER FLASHINGS FULL HEIGHT. INSTALL FULLY ADHERED FLASHING AND TIE-IN TO FIELD MEMBRANE ON BOTH SIDES OF TRANSITION
- E6** - 2'-8" (H) AREA DIVIDER. REMOVE EXISTING CLAY TILE COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL NEW 2X12 P.T. BLOCKING ON TOP OF MASONRY WALL. INSTALL 1/2" MECH ATTACHED DENS DECK OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN OPPOSITE FACE, TIE - INTO FIELD MEMBRANE ON BOTH SIDES OF WALL
- E7** - 4'-10" (H) TO 9'-0" (HXVARIES) X 1'-1" (W) ARCHD TOP PARAPET WALL. REMOVE EXISTING METAL COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL 1/2" MECH ATTACHED DENS DECK OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (ARCHD) (SEE DET. 0001) (NOTE: INSTALL INTERMEDIATE HORIZ. TERM BAR IF REQUIRED BY MFR DUE TO WALL HEIGHT)

----- CENTERLINE OF 2'-0" WIDE WALKWAY PATH  
APPROX. 1,000 LINEAL FEET

### PENETRATIONS LIST:

- CURBS**
- A - RTU ON (2) 5'6" ESC WITH 2'X3' THRU ROOF DUCT
- D - 10'X10' RTU
- E - 6'X11' RTU
- F - 7'X10' RTU
- K - 4'X7' RTU
- L - 7'X14' RTU
- EQUIPMENT SUPPORT CURBS**
- B - RTU ON (2) 21' ESC WITH 1'9"X3' UTILITY HOOD
- G - CHILLER UNIT ON (2) 21' ESC
- H - CHILLER UNIT ON (2) 11' ESC
- I - CHILLER UNIT ON (2) 20' ESC
- J - RTU ON 5'X8' I-BEAMS WITH (2) 5" ROUND POSTS WITH 1'X1' UTILITY HOOD
- RTVS**
- 3'X3' - 4
- 2'X2' - 4
- C - 5'X5' - 2
- 4'6"X4'6" - 1
- 1'9"X1'9" - 2
- ABANDONED CURBS**
- 1'X1' - 1
- 2'6"X2'6" - 3
- 3'X3' - 3
- 1'9"X1'9" - 2
- 6' ESC - 2
- 17' ESC - 2
- 1' ESC - 3
- 1'6"X1'6" - 1
- 8'6" ESC - 2
- 22' ESC - 2
- 2'X3' - 1
- 1'6"X1'6" - 1
- UTILITY HOODS**
- 1'6"X2'6" - 2
- 2'6"X2'6" - 1
- SATELLITE DISH**
- 2'6"X2'6" CURB (CAP WITH M" PLYWOOD AND ENCAPSULATE W/ MEMBRANE)
- KITCHEN EXHAUST FANS**
- 19"X19" - 1
- 3'X3' - 1
- 2'X2' - 1
- 2'6"X2'6" - 2
- GOOSE NECKED VENTS**
- 4'X4' - 1
- MANUFACTURED ESC NOT PENETRATING ROOF**
- 4' - 11
- VENT STACKS**
- 8" - 1
- 1'6"X1'6" CURB WITH 8" VENT STACK - 3
- 1'6"X2' CURB WITH 8" VENT STACK
- 1'6"X1'6" CURB WITH 10" VENT STACK
- PIPES**
- 1" - 6
- 2" - 4
- 3" - 3
- 4" - 15
- 5" - 3
- MISC**
- 4'6"X10'6" I BEAMS ON (4) 4" ROUND POSTS AND (2) 5" ROUND POSTS (ABANDONED - REMOVE)
- 4'6"X13' I BEAMS ON (8) 5" ROUND POSTS (ABANDONED - REMOVE)
- WALL SUPPORTS**
- (2) 2" FENCE POSTS IN (2) PITCH BOXES
- (14) WALL SUPPORTS ON 2'6" ESC
- ROOF HATCH (REPLACE)**
- 3'X5'

### General Notes



DISCLAIMER  
ALL DEAD, DESIGNED ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKS SHALL BE USED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.  
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

**Firm Name and Address**  
RoofingProjects.com  
17 High Street  
Suite 301  
Norwalk, CT  
06851

**Project Name and Address**  
2025  
Jewel-Osco # 157  
Oak Lawn  
4650 W 103rd St  
Oak Lawn, IL 60453

Project	Sheet
Date March 27, 2025	1
Scale 3/32" = 1'-0"	