



INSTALL NEW WALL MOUNTED GALV'D STEEL LADDER (4'-0" H) BETWEEN ROOF LEVELS WITH PLATFORM AT TOP OVER NEW GUTTER (EXACT LOCATION TO BE DETERMINED DURING PRE-CONSTRUCTION MEETING)

- EDGE CONDITION LEGEND**
- (E1) 0'-8" (H) TO 8'-0" (HXVARIES) X 0'-8" TO 1'-0" (WXVARIES) PARAPET WALL. REMOVE EXISTING METAL COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL MECH ATTACHED 1/2" DEN'S DECK OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW 2" PIECE METAL FASCIA (SEE DET. 0003)
 - (E2) 1'-4" (H) VERT. TRANSITION BETWEEN ROOF AREAS. GRAVEL STOP EDGE METAL. REMOVE EXISTING EDGE METAL AND ALL FLASHINGS. INSTALL MECH ATTACHED 1/2" DEN'S DECK OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM. INSTALL FULLY ADHERED FLASHING FULL HEIGHT AND TIE INTO FIELD MEMBRANE ON BOTH SIDES OF TRANSITION
 - (E3) 7'-0" TO 15'-0" (H) (VARIES) EXISTING SLOPED WALL WITH ASPHALT SHINGLES. INSTALL MECH ATTACHED 1/2" DEN'S DECK OVER SHINGLES FULL HEIGHT. INSTALL ADHERED WALL FLASHING OVER ENTIRE REAR SURFACE OF SLOPED WALL FULL HEIGHT. INSTALL TERM BAR, SEALANT AND SLIP FLASHING UNDER EXISTING METAL RIDGE OR RAKE TRIM (SEE DET. 0002) NOTE: REPLACE ALL EXISTING WALL VENTS IN THE EXISTING SHINGLE AREA AND FLASH INTO NEW ROOF SYSTEM
 - (E4) 6'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS AND LOW METAL COUNTER FLASHING. INSTALL MECH ATTACHED 1/2" DEN'S DECK OVER FLASHING SUBSTRATE FULL HEIGHT. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SURFACE MOUNTED COUNTER FLASHING WITH SEALANT A TOP TIGHT TO EXISTING SOFFIT (SEE DET. 0003)
 - (E5) 1'-0" (H) X 1'-0" (W) RAISED EXP. JOINT. REMOVE EXISTING WALL FLASHINGS & RAISED EXP. JOINT CAP. INSTALL MECH ATTACHED 1/2" DEN'S DECK OVER WALL FLASHINGS SUBSTRATE. INSTALL FULLY ADHERED FLASHING ON BOTH SIDES, EXTENDING OVER HORIZ. TOP OF CURB ON BOTH SIDES (EXISTING EXP. JOINT MATERIAL TO REMAIN) INSTALL NEW METAL CAP TO MATCH EXISTING CONFIGURATION

- (E6) REMOVE EXIST. DRIP EDGE METAL AND GUTTER. INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM. TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT FORDING ALONG ROOF EDGE. INSTALL NEW 8" X 8" BOX GUTTER W/ DOWNSPOUTS IN ORIGINAL LOCATIONS (SEE DET. 0004)
- (E7) 1'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS AND METAL COUNTER FLASHING. INSTALL MECH ATTACHED 1/2" DEN'S DECK OVER FLASHING SUBSTRATE FULL HEIGHT. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SURFACE MOUNTED COUNTER FLASHING WITH SEALANT A TOP (SEE DET. 0003)
- (E8) 4'-0" (H) VERT. TRANSITION BETWEEN ROOF AREAS. REMOVE ALL FLASHINGS. INSTALL MECH ATTACHED 1/2" DEN'S DECK OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED FLASHING FULL HEIGHT AND EXTEND UNDER DRIP EDGE METAL NOTED IN EDGE DETAIL E1 OR E6. INSTALL TERM BAR AND SEALANT PRIOR TO INSTALLING EDGE CONDITION E1 OR E6

--- CENTERLINE OF 2'-0" WIDE WALKWAY PATH APPROX. 1.680 LINEAL FEET

ROOF PLAN

- PENETRATIONS LIST:**
- CURBS**
 - A - RTU ON (2) 5" ESC WITH 2X3" THRU ROOF DUCT
 - D - 10'X10' RTU
 - E - 6'X6' RTU
 - F - 7'X10' RTU
 - K - 4'X7' RTU
 - L - 7'X10' RTU
 - EQUIPMENT SUPPORT CURBS**
 - B - RTU ON (2) 21" ESC WITH 13"X13" UTILITY HOOD
 - G - CHILLER UNIT ON (2) 21" ESC
 - H - CHILLER UNIT ON (2) 11" ESC
 - I - CHILLER UNIT ON (2) 20" ESC
 - J - RTU ON 5'X8" BEAMS WITH (2) 4" AND (2) 5" ROUND POSTS WITH 1X1" UTILITY HOOD
 - RTVS**
 - 3'X3' - 4
 - 2'X2' - 4
 - C - 3'X3' - 2
 - 4'6"X4'6" - 1
 - 1'9"X1'9" - 2
 - ABANDONED CURBS**
 - 1'X1' - 1
 - 2'6"X2'6" - 3
 - 3'X3' - 3
 - 1'9"X1'9" - 2
 - 0' ESC - 2
 - 17' ESC - 2
 - 1' ESC - 3
 - 1'6"X1'6" - 1
 - 8'5" ESC - 2
 - 22' ESC - 2
 - 2'5" - 1
 - 1'6"X1'6" - 1
 - WALL SUPPORTS**
 - (2) 2" FENCE POSTS IN (2) PITCH BOSES
 - (14) WALL SUPPORTS ON 2'6" ESC
 - ROOF HATCH (2) (REPLACE)**
 - 3'X3'
 - UTILITY HOODS**
 - 1'6"X2'6" - 2
 - 2'6"X2'6" - 1
 - SATELLITE DISH**
 - 2'6"X2'6" CURB (REMOVE)
 - KITCHEN EXHAUST FANS**
 - 1'9"X1'9" - 1
 - 3'X3' - 1
 - 2'X2' - 1
 - 2'6"X2'6" - 2
 - GOOSE NECKED VENTS**
 - 4'X4' - 1
 - MANUFACTURED ESC NOT PENETRATING ROOF FLASH INTO NEW ROOF)**
 - 4'-13"
 - VENT STACKS**
 - 8'-1"
 - 1'6"X1'6" CURB WITH 8" VENT STACK - 3
 - 1'6"X2" CURB WITH 8" VENT STACK
 - 1'6"X3'6" CURB WITH 30" VENT STACK
 - PIPES**
 - 1'-6"
 - 2'-4"
 - 3'-3"
 - 4'-15"
 - 5'-3"
 - MISC**
 - 4'5"X10'6" BEAMS ON (4) 4" ROUND POSTS AND (2) 5" ROUND POSTS (ABANDONED) (REMOVE)
 - 4'5"X11' BEAMS ON (8) 5" ROUND POSTS (ABANDONED) (REMOVE)

General Notes

DISCLAIMER

ALL DEAD, DESIGNED ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKS SHALL BE USED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.

WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.



No.	Revision/Issue	Date

Firm Name and Address

RoofingProjects.com
 17 High Street
 Suite 301
 Norwalk, CT
 06851

Project Name and Address

2025
 Jewel-Osco #2313
 Elgin
 1660 Larkin Ave
 Elgin, IL 60123

Project	Sheet
Date	1
March 27, 2025	
Scale	
1/16" = 1'-0"	