



ROOF PLAN

--- CENTERLINE OF 2'-0" WIDE WALKWAY PATH
APPROX. 1,080 LINEAL FEET

EDGE CONDITION LEGEND

- Ⓔ- EX. 0'-6" (W) X 0'-8" (H) RAISED EXP. JOINT. REMOVE EXISTING WALL FLASHINGS & RAISED EXP. JOINT CAP & JOINT. INSTALL FOAM RDD 1 1/2 TIMES WIDTH OF JOINT AND INSTALL FULLY ADHERED FLASHING UP OVER AND DOWN OPPOSITE FACE AND TIE INTO THE FIELD OF ROOF ON BOTH SIDES.
- Ⓔ- 0'-8" (H) TO 3'-6" (H)(VARIES) X 1'-0" (W) TO 1'-6" (W)(VARIES) PARAPET WALL. REMOVE EXISTING METAL COPING AND WALL FLASHINGS. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- Ⓔ- 9'-0" SLOPED FLASHING TO 1'-0" TO 9'-0" (H)(VARIES) X 1'-0" (W) TO 1'-6" (W)(VARIES) PARAPET WALL. REMOVE EXISTING METAL COPING AND VERTICAL WALL FLASHINGS LEAVING SLOPED FLASHINGS IN PLACE. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER SLOPED FLASHINGS AND VERT. FLASHING SUBSTRATE FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- Ⓔ- 1'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS. INSTALL 1/2" DENS DECK MECH. ATTACHED OVER FLASHING SUBSTRATE. FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET. 0002)

PENETRATIONS LIST:

- CURBS**
- A - 3'6"X6'6" RTU
- B - 6'X8' RTU
- C - CONDENSER ON (2) 3' (L) EQ SUPPORT CURBS
- D - 3'6"X7' RTU
- E - 8'X2' RTU
- F - 9'6"X9'6" (1'H RAISED AREA - REMOVE CURB FLASHINGS AND GRAVEL, INSTALL DENS DECK ON WALL FLASHINGS AND SPECIFIED RECOVERY BOARD OVER TOP AND ENCAPSULATE WITH MEMBRANE)
- G - 8'X15' CAPPED CURB - REMOVE, CLOSE OPENING IN DECK INFILL INSULATION TO MATCH HEIGHT OF EXISTING ROOF AND ROOF OVER AREA
- H - CHILLER UNITS ON (5) 8" (W) X15' (L) EQUIPMENT SUPPORT CURBS
- I - CHILLER UNITS ON (3) 8" (W) X15' (L) EQUIPMENT SUPPORT CURBS
- J - 4'6"X7'6" RTV
- K - 5'X3' RTV
- L - 3'X3' RTV
- M - 8'X32' RTU
- RH - 2'9"X4'9" ROOF HATCH (REPLACE)
- RTVS**
- 1'9"X1'9" - 3
- 2'X2' - 3
- 3'X3' - 3
- PIPES**
- 5" - 23
- 6" - 3
- UTILITY HOODS**
- 1'9"X1'9" - 3
- UTILITY HOOD CURB**
- 1'X1' - 2
- VENT STACK CURB**
- 1'X1' - 7
- 1'6"X1'6" - 2
- KITCHEN EXHAUST CURB**
- 1'9"X1'9" - 4
- SAT DISH POLE**
- 1'X1' REMOVE
- ABANDONED CURB - REMOVE, CLOSE OPENING IN DECK INFILL INSULATION TO MATCH HEIGHT OF EXISTING ROOF AND ROOF OVER AREA**
- 1'X1' - 1

General Notes



DISCLAIMER
ALL DEAD, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY, AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGNS, ARRANGEMENTS OR MARKS SHALL BE USED BY OR DISCLOSED TO ANY PARTISER WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address
 RoofingProjects-com
 17 High Street
 Suite 301
 Norwalk, CT
 06851

Project Name and Address
 2025
 Jewel-Osco #3343
 375 S Randall Rd
 South Elgin, IL 60177

Project	Sheet
Date April 11, 2025	1
Scale 1/16" = 1'-0"	