



**EDGE CONDITION LEGEND**

- E1- 1'-6" (H) TO 2'-6" (HXVARIES) X 0'-8" (W) TO 1'-1" (WXVARIES) PARAPET WALL. REMOVE EXISTING METAL COPING AND WALL FLASHINGS. INSTALL MECH ATTACHED 1/2" DENS DECK OVER FLASHING SUBSTRATE. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)
- E2- 10" (H) X 10" (W) RAISED EXP. JOINT. REMOVE EXISTING METAL CAP. REMOVE EXISTING WALL FLASHINGS AND EXP. JOINT. INSTALL MECH ATTACHED 1/2" DENS DECK OVER FLASHING SUBSTRATE. INSTALL FDM RDD 1 1/2 TIMES WIDTH OF JOINT AND INSTALL FULLY ADHERED FLASHING UP OVER AND ONTO OPPOSITE FACE WITH SEALANT AND TERM BAR. INSTALL NEW METAL JOINT CAP TO MATCH EXISTING PROFILE AND CONFIGURATION
- E3- 1'-0" (H) WALL FLASHING. REMOVE EXISTING FLASHINGS, METAL COUNTER FLASHING. INSTALL MECH. ATTACHED 1/2" DENS DECK OVER FLASHING SUBSTRATE. INSTALL FULLY ADHERED WALL FLASHING AND NEW TERM BAR SEALANT AND SURFACE MOUNTED COUNTER FLASHING WITH SEALANT JOINT AT TOP (SEE DET. 0002)
- E4- GRAVEL STOP EDGE METAL. REMOVE EXISTING EDGE METAL. INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM & NEW GRAVEL STOP EDGE METAL W/ FULLY ADHERED FLASHING (SEE DET 0002)
- E5- 2'-2" (H) TO 6'-0" (HXVARIES) X 0'-9" (W) TO 3'-0" (WXVARIES) PARAPET WALL. REMOVE EXISTING METAL COPING AND BASE WALL FLASHING LEAVING METAL WALL PANELS IN PLACE. FURR-DUT BASE FLASHING AREA TO BE FLUSH W/ METAL PANELS ABOVE. INSTALL MECH ATTACHED 1/2" DENS DECK OVER METAL PANELS FULL HEIGHT. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE, INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0001)

**PENETRATIONS LIST:**

- RTU**  
A - 4'x6" RTU ON (2) 5' EQUIP. SUPPORT CURB WITH (2) 1'6"x1'6" THRU ROOF DUCTS  
C - 7'x13'6"
- RTV**  
2'6"x2'6" - 4  
B - 4'x4'6" - 1  
1'9"x1'9" - 2  
D - 6'x6"
- VENT STACKS**  
8" ROUND - 2
- ABANDONED CURBS (REMOVE, CLOSE OPENING IN DECK AND ROOF OVER AREA)**  
2'3"x2'3" - 1  
2'8"x2'8" - 1

**CONDENSERS**

- CONDENSER ON (2) 4'6" WOOD DUNNAGE (REPLACE WOOD DUNNAGE W/ PT LUMBER AND SET ON WALK PADS)

**WALL SUPPORTS**

- 10"x2" POURABLE SEALER POCKET (19 TOTAL)

**PIPES**

- 1" - 13
- 2" - 9
- 3" - 5
- 4" - 4

**SATELLITE DISH BASE SUPPORTS**

- 2'x3' - 1
- 5" POST
- 10"x10" POURABLE SEALER POCKETS (3)
- 6" x6" POURABLE SEALER POCKETS
- 4" POST

**EQUIPMENT SUPPORT CURBS FOR PIPE SUPPORTS**

- 6'x1'6" - 20

**NOTE:**

NEW MEMBRANE SHEETS MUST BE INSTALLED PERPENDICULAR TO THE STEEL DECK FLUTES (NOT REQUIRED IF UTILIZING ACCEPTED RHINO BOND ATTACHMENT METHOD)



DISCLAIMER  
ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY, AND ARE THE PROPERTY OF ROOFINGPROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH DESIGN, ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF ROOFINGPROJECTS.COM.  
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

**Firm Name and Address**  
RoofingProjects-com  
17 High Street  
Suite 301  
Norwalk, CT  
06851

**Project Name and Address**  
2025  
Radiant Partners  
JC Penny  
3437 Masonic Drive,  
Alexandria, LA 71301

Project	Sheet
Date May 27, 2025	1
Scale 1/16" = 1'-0"	