



ROOF PLAN

EDGE CONDITION LEGEND

- Ⓚ - 8" (H) TO 9" (H) (VARIES) X 6" (W) RAISED EXP. JOINT. REMOVE EXISTING WALL FLASHINGS ON CONTRACT SIDE & RAISED EXP. JOINT CAP & JOINT. INSTALL 1/2" DENS DECK OVER SUBSTRATE. INSTALL FOAM ROD 1 1/2 TIMES WIDTH OF JOINT AND INSTALL FULLY ADHERED FLASHING UP OVER AND INTO OPPOSITE FACE AND INSTALL TERM BAR AND SEALANT
- Ⓚ - 0'-5" TO 1'-10" (H) WALL FLASHING. REMOVE FLASHINGS. INSTALL 1/2" DENS DECK OVER SUBSTRATE AND FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND SLIP FLASHING TO BACKSIDE EXISTING METAL COUNTER FLASHING TO REMAIN (SEE DET. 0001)
- Ⓚ - 1'-0" (H) WALL FLASHING. REMOVE ALL FLASHINGS. INSTALL 1/2" DENS DECK OVER SUBSTRATE AND FULLY ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT JOINT (SEE DET. 0002)
- Ⓚ - 1'-4" TO 1'-4" (H) (VARIES) WALL FLASHING. REMOVE FLASHINGS. ROOF TO WALL EXPANSION JOINT AND METAL COUNTERFLASHING. INSTALL 1/2" DENS DECK OVER SUBSTRATE. INSTALL FOAM ROD 1 1/2 TIMES WIDTH OF JOINT OPENING. INSTALL FULLY ADHERED WALL FLASHING. INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING (SEE DET. 0002)
- NOTE: INSTALL NEW SKIM COAT SEALANT AT ALL VERT. CONC. WALL JOINTS ABOVE COUNTER FLASHING
- Ⓚ - 8" TO 2'-4" (H) (VARIES) WALL FLASHING. REMOVE FLASHINGS. AND METAL COUNTERFLASHING. INSTALL 1/2" DENS DECK OVER SUBSTRATE. INSTALL FULLY ADHERED WALL FLASHING. INSTALL TERM BAR, SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING (SEE DET. 0002)
- Ⓚ - ROOF LEVEL EXP. JOINT. REMOVE EXISTING FLASHINGS & EXP. JOINT. INSTALL FOAM ROD 1 1/2 TIMES WIDTH OF JOINT AND INSTALL FULLY ADHERED FLASHING OVER JOINT AND TIE INTO THE FIELD OF ROOF ON BOTH SIDES
- Ⓚ - 1'-0" TO 1'-4" (H) WALL FLASHING. REMOVE FLASHINGS. ADHERE NEW WALL FLASHING. INSTALL TERM BAR, SEALANT UNDER NEW FASCIA CLEAT AT TOP OF WALL (SEE EDGE CONDITION ON ADJACENT SECTION A)
- Ⓚ - 8" (H) TO 5'-8" (H) (VARIES) X 1'-6" (W) PARAPET WALL. REMOVE EXISTING METAL COPING, WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL 1/2" DENS DECK OVER SUBSTRATE. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET. 0003)
- Ⓚ - GRAVEL STOP EDGE METAL. REMOVE EXISTING EDGE METAL. INSTALL NEW WOOD BLOCKING TO MATCH HEIGHT OF NEW ROOF SYSTEM & NEW GRAVEL STOP EDGE METAL W/ FULLY ADHERED FLASHING (SEE DET. 0004)
- Ⓚ - 10'-8" (H) PARAPET WALL. REMOVE EXISTING WALL FLASHINGS AND ANY LOW METAL COUNTER FLASHING. INSTALL 1/2" DENS DECK OVER SUBSTRATE. INSTALL FULLY ADHERED WALL FLASHING FULL HEIGHT AND TIE INTO UPPER ROOF MEMBRANE

PENETRATIONS LIST:

SECTION A

CURBS

- A - 5'X7' RTU
- B - 7'X12' RTU
- D - 5'X9' RTU

RTVS

- 1'6"X16" - 1

PIPES

- 1" - 3
- 2" - 1
- 4" - 1

SAT DISH ON PAD (SET ON WALK PADS)

- 4'X4' - 1
- 2'X3' - 2

VENT STACK

- 6" - 1
- 8" - 1

CONDENSERS

- 2'-6" WOOD DUNNAGE - 1 (REPLACE WOOD DUNNAGE W/ NEW PT WOOD SET ON WALK PADS)

ABANDONED CURB (REMOVE CURB, CLOSE OPENING IN DECK, INFILL INSULATION TO MATCH HEIGHT OF EXISTING ROOF SYSTEM AND ROOF OVER AREA)

- 1" - 5'X5'
- (2) LARGE RTVS DISCONNECTED ON ROOF SURFACE - REMOVE

PENETRATIONS LIST:

SECTION B

CURBS

- A - 4'6"X12' RTU
- B - 5'X7'6" RTU
- C - 4'X8' RTU
- D - 6'6"X15' RTU
- E - 5'X9' RTU
- F - 4'X6' RTU

PIPES

- 1" - 13
- 2" - 5
- 3" - 5
- 4" - 4

VENT STACK

- 6" - 7
- 8" - 2

SAT DISH ON PAD (SET ON WALK PADS)

- 3'X3' - 2
- 5'6"X5'6" - 1

ABANDONED CURB (REMOVE CURB, CLOSE OPENING IN DECK, INFILL INSULATION TO MATCH HEIGHT OF EXISTING ROOF SYSTEM AND ROOF OVER AREA)

- 1'9"X1'9" - 1
- 1 DOWNSPOUT FROM ADJACENT ROOF - INSTALL WALK PAD AT DISCHARGE POINT



General Notes



DISCLAIMER
ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY, AND ARE THE PROPERTY OF RP ROOFING PROJECTS.COM AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH LOGOS, DESIGN, ARRANGEMENTS OR PLANS SHALL BE USED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF RP ROOFING PROJECTS.COM.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

| No. | Revision/Issue | Date |
|-----|----------------|------|
| | | |

Firm Name and Address
RoofingProjects.com
17 High Street
Suite 301
Norwalk, CT
06851

Project Name and Address
2026
Radiant Partners
Sunset Mall
4001 Sunset Dr #1182
San Angelo, TX 76904

| | |
|----------------------------|-------|
| Project | Sheet |
| Date January 12th, 2026 | 1 |
| Scale 1/16" = 1'-0" | |