



EDGE CONDITION LEGEND

- E1 - 0'-6" TO 5'-0" (HX/VARIES) X 1'-0" TO 3'-0" (WX/VARIES) PARAPET WALL. REMOVE EXISTING EDGE METAL AND WALL FLASHINGS. INSTALL FULLY ADHERED WALL FLASHING UP OVER EXIST. TOP PLATE AND DOWN FRONT FACE. INSTALL NEW TWO PIECE METAL FASCIA (SEE DET 0001)
- E2 - RAISED GRAVEL STOP EDGE METAL. REMOVE EXISTING EDGE METAL. INSTALL NEW GRAVEL STOP EDGE METAL W/ FULLY ADHERED FLASHING (SEE DET 0002)
- E3 - 1'-0" TO 4'-0" (HX/VARIES) WALL FLASHING. REMOVE FLASHINGS. ROOF TO WALL EXPANSION JOINT. INSTALL FEAM ROD 1 1/2"X WIDTH OF JOINT OPENING. INSTALL FULLY ADHERED WALL FLASHING. INSTALL TERM BAR. SEALANT AT TOP (INSTALL UNDER NEW GRAVEL STOP EDGE METAL AT TOP OF WALL (SEE EDGE CONDITION E2)
- E4 - REMOVE EXIST. DRIP EDGE METAL AND GUTTER. INSTALL NEW WOOD BLOCKING AND TAPERED EDGE STRIP TO MATCH HEIGHT OF NEW ROOF SYSTEM. TO PROMOTE DRAINAGE INTO GUTTER AND PREVENT PONDING ALONG ROOF EDGE. INSTALL NEW 10" X 10" BOX GUTTER W/ (6) DOWNSPOUTS IN ORIGINAL LOCATIONS TO MATCH EXISTING CONFIGURATION (SEE DET 0001)
- E5 - CUT BOTTOM EDGE OF EIFS WALL CLADDING TO FACILITATE AN 8" MIN. FLASHING HEIGHT (WHERE NEEDED TO MAINTAIN 8" FLASHING HEIGHT) AND SEAL CUT EDGE. REMOVE EXISTING FLASHINGS. INSTALL 8"(H) FULLY ADHERED WALL FLASHING. TERM BAR W/ SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT AT TOP TIGHT TO BOTTOM OF EIFS WALL CLADDING (SEE DET. 0004)
- E6 - 3'-6" (H) TRANSITION BETWEEN ROOF LEVELS REMOVE EXIST. WALL FLASHINGS. INSTALL NEW ADHERED FLASHING FULL HEIGHT AND TIE-INTO FIELD MEMBRANE ON BOTH SIDES OF VERT. TRANSITION
- E7 - REMOVE EXISTING FLASHINGS. INSTALL 8"(H) FULLY ADHERED WALL FLASHING. TERM BAR W/ SEALANT AND NEW SURFACE MOUNTED COUNTER FLASHING W/ SEALANT AT TOP (SEE DET. 0004)

PENETRATIONS LIST:

SECTIONS A, B & C:

- CURBS**
- A - 7.5X5' RTU
- B - 10X46 RTU
- C - 4X7' RTU
- D - 3.5X6.5' RTU
- E - 5X4' RTU
- F - 4X3' RTV
- H - 3.5X3' HATCH (REPLACE)

PIPE PENETRATIONS

- 1" - 25
- 2" - 4
- 3" - 10
- 4" - 7
- 19"X3' CONDENSER CURB - 1
- 1" WIDE ROUND VENT STACK - 1
- 2X2' RTV - 2
- 1.5X1.5' RTV - 9
- 7X7' SAT DISH PAD - 1
- 1.5X1.5' ABANDONED CURB - 3 (REMOVE. CLOSE OPENING IN DECK. INFILL INSULATION TO MATCH EXISTING ROOF HEIGHT AND ROOF OVER AREA)

- 8" ROUND VENT STACK - 3
- 16" ROUND VENT STACK - 1

- (6) 5X5" EQUIPMENT SUPPORT POSTS
- (2) 9"X9" EQUIPMENT SUPPORT POSTS
- 2X2' UTILITY BOX WITH CONDUITS - 4

SECTION D:

- CURBS**
- A - 4.5X7' RTU
- B - 4X7' RTU
- H - 3"X3.5' HATCH (REPLACE)

PIPE PENETRATIONS

- 1" - 2
- 4" - 1
- 16"X16" RTU - 5
- 19"X19" RTV - 1
- 2X2' RTU - 1
- 10"X10" SAT DISH PAD - 1 (SET ON WALK PADS)
- 8" ROUND VENT STACK - 1

ROOF PLAN

General Notes



DISCLAIMER
ALL DESIGN, DESIGN ARRANGEMENTS, AND PLANS INDICATED OR REPRESENTED BY THIS DRAWING ARE OWNED BY AND ARE THE PROPERTY OF RP ROOFING PROJECTS, LLC AND WERE CREATED, EVOLVED AND DEVELOPED FOR USE ON AND IN CONNECTION WITH THE SPECIFIED PROJECT. NONE OF SUCH DESIGN, ARRANGEMENTS OR PLANS SHALL BE LOANED BY OR DISCLOSED TO ANY THIRD PARTY WITHOUT THE WRITTEN PERMISSION OF RP ROOFING PROJECTS, LLC.
WRITTEN DIMENSIONS ON THIS DRAWING SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS.

No.	Revision/Issue	Date

Firm Name and Address
RoofingProjects-com
17 High Street
Suite 301
Norwalk, CT
06851

Project Name and Address
2025
Shaws #1402
1400 Lakeshore Dr
Gilford, NH 03249
SUMMIT REALTY PARTNERS
WINSLOW PROPERTY MANAGEMENT

<small>Project</small>	<small>Sheet</small>
<small>Date</small> June 25, 2025	1
<small>Scale</small> 1/16" = 1'-0"	